

Appendix A

Page 1 of 3

Our Ref: S35919
Your Ref:

20 December 2024

Ian Bovis
Service Delivery Manager
Saltash Town Council
Saltash
PL12 6JX

Dear Ian

QUOTATION REQUEST: ROM PRICE FOR PHAZE 1 REGARDING STORM DAMAGE TO PONTOON SYSTEM

Many thanks for your recent enquiry and I am pleased to offer as per the attached costing schedule.

I trust the enclosed details are to your satisfaction. Should you require further information or clarification please do not hesitate to contact me.

Kind regards,

S35919 Quotation

Item	Description – Saltash Pontoon System	Quantity	Unit Price	Total Price
1.00	<p>To supply skilled labour, plant, tools & equipment to:</p> <ul style="list-style-type: none"> • Carry out initial survey to assess storm damage • Produce survey report and proposed actions • Manufacture a brow support beam • Weld support beam brackets to existing piles • Lift the access brow using a suitable crane and lower on brow support beam • Disconnect the 4 finger pontoons from the main pontoon • Attache a finger pontoon to a workboat and toe to the adjacent slipway • Repeat for 3 remaining finger pontoons • Disconnect the outer main pontoon from the piles • Attache the pontoon to a workboat and tow to the adjacent slipway • Disconnect the brow pontoon from the piles • Attach the pontoon to a workboat and tow to the adjacent slipway • Pressure wash and clean marine growth for all the pontoons • Remove the decking from all the pontoons • Survey the deck structure on all the pontoons • Pressure test each pontoon and survey • NDT all the pontoon connection points • Produce a full survey report on findings • Propose actions <p>Sub-Contract Hire:</p> <ul style="list-style-type: none"> • Crane • Work Boat • Compressor • Pressure washer 	1.00		£20,000.00
		1.00		£4,000.00
		1.00		£2,000.00
		1.00		£250.00
		1.00		£200.00
Total Price For Works				£26,450.00
<p>Remarks :</p> <p>Payment Terms : 30 days from date of invoice</p>				

Value Added Tax : All prices quoted exclude VAT and must be added, where applicable

Price Validity : 30 days