

Appendix B



Jubilee Pontoon Repairs Estimate

Phase 1

Thursday 13 February 2025

7 Pages Identified

Voyager Boatyard Jubilee Pontoon Damage Repair Estimate for Phase 1 Works

Assigned To Saltash Town Council

SALTASH JUBILEE PONTOON

Assigned To Saltash Town Council

1. De risk current situation by securing the hammerhead pontoon to the main pontoon with heavy chains and shackles, this will a very positive step to prevent the pontoon system from breaking free.
2. Supply and deploy towboat(s) and safety boat with suitable labour force
3. Detach each finger pontoon and tow to Voyager Boatyard
4. Pontoon services will need to be isolated
5. Split down and detach hammerhead pontoon and tow to Voyager Boatyard
6. Attach support brackets and steel channel to walkway piles, lift and lower gangway to the channel
7. Supply and fit safety chain to fix gangway to the piles to provide additional safety
8. Detach and tow main pontoon to Voyager Boatyard
9. Lift each pontoon system with boat travel hoist and slip
10. Scrape and power wash pontoon system and steel floats
11. Remove deck and sub structure from main floats
12. Produce a full survey of the steel work to include Ultrasonic Thickness Measurements (UTMs) of the steel floats and Non Destructive Testing (NDT) of the connection points
13. Produce a report and quotation for Phase 2 works which will be the repair and refurbishment of the pontoon system to put her back into a serviceable condition
14. Storage of pontoon system for 28 days at Voyager Boatyard
15. Voyager Boatyard can start the Phase 1 works next week, week commencing 24th Feb, we believe a quick start is vital to de risk the possibility of the pontoon system breaking free, we are still prone to heavy weather and storms this time of year.

Price for Phase 1 works
£24,950 + VAT



Jubilee Pontoon
Assigned To Saltash Town Council



Jubilee Pontoon
Assigned To Saltash Town Council



Jubilee Pontoon
Assigned To Saltash Town Council



Jubilee Pontoon
Assigned To Saltash Town Council

