

Company B

Our Reference; C25405

Saltash Town Council
The Guildhall
12 Lower Fore Street
Saltash
PL12 6JX

27TH August 2025

For the attention of; -

Reference; - Isambard House, Saltash Railway Station

Thank you for your enquiry. I am writing to present our quotation for the following works.

Main Hall, Corridor & Cafe

Degreasing of existing floor surface with FBall C140 Cleaner.

Supply and installation of FBall P141 Primer to subfloor.

Supply and installation of 3mm Coat of Latex Smoothing Compound.

Supply and installation of 'Lobby' Entrance Matting x 2Nr.

Supply and installation of Forbo Surestep R11 Vinyl – Colour Concrete.

Supply and installation of 2Nr Double Door Threshold Trims.

Package Total £8,564.74 + VAT

Clarifications

- Areas to be cleared by others, prior to the commencement of works.
- Quotation based upon standard working hours 8-16.30 Monday – Friday.
- MDF Skirtings to be supplied and installed by others.
- Resin cracks can be repaired with Mapei Eporip. This shall be chargeable at £120.00.

Should you have any queries or require any further information, please do not hesitate to contact me.

Assuring you of my best endeavour's.

Surveyor & Estimator

Lang and Potter (Flooring) Ltd