



QUOTE



Date
22 Aug 2023



Description	Quantity	Unit Price	VAT	Amount GBP
Proposed deck replacement of Saltash pontoon.	1.00	10,125.00	20%	10,125.00
<p>To remove all existing deck boards (approximately 65m long). Remove sub timbers to metal frame work. Dispose of all existing timber deck and frame.</p> <p>Supply and fit treated timber subframe. Supply and fit hardwood deck boards to new frame work.</p> <p>All timber subframe to be bolted with stainless steel bolts, washers and nuts. All deck boards to be fixed on both edges to lower frame work with 50mm stainless steel 10 gauge screws.</p> <p>This will provide a long lasting frame and deck set up to the pontoon.</p> <p>Ensure all working areas are safe when work is in progress and once complete clear all waste materials from site.</p>				
			Subtotal	10,125.00
			TOTAL VAT 20%	2,025.00
			TOTAL GBP	12,150.00