

COMPANY C

Quotation

Date: 11th September 2023
Ref: Saltash Train Station, Saltash

With reference to the resurfacing of the parking area at Saltash Train Station.

We would excavate the whole parking area and path. Reinststate with type 1 subbase where necessary.

A galvanised steel rail would be installed along the wall preventing cars damaging the wall.

Install 3 removable locking Cornwall Cast Iron security bollards along the entrance to match the existing bollards.

Remove all tree stumps and iron works from site.

The prepared area would have a 20 mm tarmac base coat and overlaid with a tarmac wearing course.

Reinststate the disabled parking bay line markings and add additional 6 car spaces.

All waste materials shall be removed off site.

Quotation prices are upheld for 60 days from date of quotation.

Sub Total	£16,650
VAT 20%	£ 3,330
Total	£19,980