

COMPANY C

Preliminary estimate for repair/services to the Saltash town centre, Jubilee 2002 public wall clock.

Note,

It is not possible for me to submit an accurate quote for the services needed to restore this clock to good working order, until the clock dials have been removed, and the mechanisms and electrical system examined.

I recently visited the clock to assess, finding the hands of both dials stopped and showing different times.

After investigation and tampering with the 'electrical control unit' in place there, the west facing hands began to work and self-corrected to the correct time. Therefore, it may only be necessary to replace one of the movements.

The cost for that visit has been included in the estimate.

To.

Hire and erect a self-assembling scaffold rig.

Remove both dial covers, dials and seals, examine for signs of rainwater intrusion, and repair if and as is necessary.

Supply and install a replacement new clock mechanism for the west facing dial and examine the clock mechanism of the east facing dial, and service/repair as and if is necessary.

If necessary, supply and install a replacement clock control system for automatic restart and time correction, and seasonal time changes.

Remove rust from the clocks wall bracket, prime and repaint.

Investigate the timed illumination system and if necessary, supply and install new, or repair if possible.

Estimate inclusive of parts and

labour..... £1100:00 - £1400:00

Note.

I must reserve the right to re-estimate if after commencement, extra work and/or parts that will incur additional cost is found to be needed.

There is no VAT to be added.